



- LOG SIZING FOR ROOF SYSTEM

REFER TO ROOF PLAN PAGE A-8
- ROOF FRAMING ASSEMBLY

ASPHALT SHINGLE
BITUMENIC
STRUCTURAL EAGLE PANELS
- EXTERIOR FRAME WALL ASSEMBLY

EXTERIOR WOOD FINISH TO CLIENT'S SPECS.
BUILDING PAPER
7/16" PLYWOOD OR OSB SHEATHING
2x6 @ 16" oc FRAME WALL
BATT INSULATION
POLY DVB
INTERIOR FINISH TO CLIENT'S SPECS
- LOFT FLOOR ASSEMBLY

3/4" FINISH FLOOR TO CLIENT'S SPECS
1/2" GYPCRETE TOPPING
3/4" PLYWOOD SUBFLOOR
2x8 JOISTS 16" oc
3/4" CEILING TO CLIENT'S SPECS
LOG FLOOR JOISTS
- INTERIOR FRAME WALLS

ALL INTERIOR FRAME WALL TO BE 2x4
@ 16" oc UNLESS NOTED OTHERWISE

NOTES

AMENDMENTS

PROJECT TITLE:

**GOLTERMAN
LOG HOME**

DESTINATION:
BRECKENRIDGE, CO

MAIN: 2620 sq. ft.
LOFT: 1630 sq. ft.

PREPARED FOR:

PREPARED BY:



CANADA DIVISION
351 HODGSON ROAD
WILLIAMS LAKE, BC
V2G 3P7 CANADA
PH (250) 392-5577
FAX (250) 392-5581
TOLL FREE: 1-877-822-5647

U.S. DIVISION
P.O. BOX 301
PAYSON, ARIZONA
85547-0301
UNITED STATES
PH (928) 472-8073
FAX (928) 474-8991
TOLL FREE: 1-877-224-4654

DRAWING TITLE:

**LOFT FLOOR
PLAN**

SCALE:

DATE:

APRIL 19, 2006

DRAWN BY:

D. FITZEL

CHECKED BY:

PAGE:

A-7

LOFT FLOOR PLAN